SATCO | NUVO



Project / Job Name:

Location:

Fixture Type:

Notes:

S12325 - 4.5 Watt T6 LED; Clear Finish; G8 Base; 5000K; 120 Volt

DAMP LOCATION · DIMMABLE · ENCLOSED FIXTURE · cULus LISTED · FC · RoHS COMPLIANT · 25,000 HOURS · 5 YEAR WARRANTY · 120 VOLT

GENERAL

Company	SATCO
EA Height	2.95
EA Width	1.5
EA Length	1.5
Candle Power	35.0
Center Beam Candle Power	35
Lamp Filament	LED
Material	Ceramic / Polycarbonate (PC)
Fixture Type	Tubular
Status	Discontinued
Style	Utility
Surge Protection	Built-in surge protection - 1.5KV
Total Harmonic Distortion	70%
CCT Selectable	No
Wattage Selectable	No
Finish Family	Clear
Amps	0.037A
Has Camera	No
IOT Enabled	No
Lens Material	Polycarbonate (PC)
Power Factor	0.9
SDS Class	LED_Lamp
Indoor Outdoor	Indoor
Product Technology	LED
Incandescent Equivalent	35W
Serviceable Battery	No
Battery Indicator	No
Digital Display	No

ELECTRICAL

CCT (Kelvin Temp)	5000K
Dimmable	Yes-Dimmable
Hours Rated	25000
Beam Angle (degree)	300
Color Temp	Natural Light
CRI	80+
Dimming Type	120V only, Phase Cut (TRIAC)
Operating Frequency	60Hz
Operating Temp	-4F to +104F (-20C to +40C)
Lumens	430L
Volts	120v
Watts	4.5W

PHYSICAL

Lamp Base	Bi Pin G8
Finish	Clear
Housing Color	White
ANSI Base	G8
Lamp Type	T6
MOD Lamps	0.73
MOL	1.77

ADDITIONAL INFO

Warranty	5-Years
Installation Notes	Not for use in vapor tight fixtures.
Rated For Enclosed Fixture	Yes

PACKAGING

UPC	045923123252
Case Cube	1.1904
Case Height	13.62
Case Length	17.44
Case Quantity	200
Case UPC	10045923123259
Case Weight	8.66
Case Width	8.66
EA Cube	0.0038
EA Height	2.95
EA Length	1.5
EA Quantity	1
EA Weight	0.033
EA Width	1.5
Inner Cube	0.1004
Inner Height	6.42
Inner Length	8.07
Inner Quantity	20
Inner UPC	20045923123256
Inner Weight	0.78
Inner Width	3.35
Pack Type	Box
Web Length	1.77
Web Width	0.73

COMPLIANCE

FCC Compliant	Yes
Location Rating	Damp
ROHS Compliant	Yes
Safety Listing	cULus - Certified, cULus - Listed
California Ban	Lawful for sale
DLC Approved	No
Title 20	Exempt
T24/JA8 Compliant	No

© Satco Products, Inc.
All rights reserved 2026